

SOLAR ASSISTED HOT WATER SYSTEM

WATERFORD WELCOME CENTER

WATERFORD, VERMONT

FINAL REPORT 86-2
August, 1986

Reporting on
Work Plan 82-R-5

State of Vermont
Agency of Transportation
Materials & Research Division

Susan C. Crampton, Secretary of Transportation
Frank E. Aldrich, P.E., Chief Engineer
R.F. Nicholson, P.E., Materials & Research Engineer

Prepared By:

P. E. Corti
Research Specialist

Reviewed By:



R.F. Nicholson, P.E.
Materials & Research Engineer

Date: 08-14-86

1. Report No.	2. Government Accession No.	3. Recipient's Catalog No.	
4. Title and Subtitle Solar Assisted Hot Water System-Waterford Welcome Center, Waterford, Vermont		5. Report Date August, 1986	
		6. Performing Organization Code	
7. Author(s) Paul E. Corti		8. Performing Organization Report No. 86-2	
9. Performing Organization Name and Address Vermont Agency of Transportation Materials & Research Division 133 State St., State Admn. Bldg. Montpelier, Vermont 05602		10. Work Unit No. DTFH 71-82-52-VT-04	
		11. Contract or Grant No.	
12. Sponsoring Agency Name and Address Federal Highway Administration Demonstration Projects Division 1000 Glebe Road Arlington, Virginia 22201		13. Type of Report and Period Covered Final Report	
		14. Sponsoring Agency Code	
15. Supplementary Notes			
16. Abstract <p>A solar system was installed on the newly constructed Welcome Center on Interstate 93 in Waterford, Vermont. Bascially, the system uses exteriorly mounted solar panels to transfer solar heat to antifreeze which transfers heat to a hot water tank by means of a heat exchanger.</p> <p>Monitoring equipment installed on the solar system revealed that 97% to 99% of the hot water used was supplied by the solar system.</p> <p>Cost of the solar system with back-up equipment was \$5755.00. Projections indicate that the cost of the system would be recovered in 10 years of service and save an estimated 58,000 kilowatt hours of electricity.</p>			
17. Key Words Solar Hot Water System		18. Distribution Statement No Restrictions	
19. Security Classif. (of this report) Unclassified	20. Security Classif. (of this page) Unclassified	21. No. of Pages 24	22. Price

ACKNOWLEDGMENT

This project was performed in cooperation with the U. S. Department of Transportation, Federal Highway Administration, Demonstration Projects Division, in conjunction with Demonstration Project No. 52, Solar Energy for Highway Uses under Work Order No. DTFH 71-82-52-VT-04.

The contents of this report reflect the views of the author who is responsible for the facts and the accuracy of the data presented herein. This report does not constitute a standard, specification or regulation. Anyone other than the Agency using this report does so with awareness that the Agency does not guarantee the opinions, findings, or conclusions contained therein.

TABLE OF CONTENTS

Introduction	1
Location and Building Description	2
Climatological Information.	3
Solar System Description	4
Monitoring Equipment and Procedures.	6
Results of Data Obtained	8
Cost and Payback of Solar System.	10
Public Information Display.	11
Summary	12
Appendix A - Location Map	13
Appendix B - Welcome Center Site Plan	14
Appendix C - Manufacturer's Description of Solar Heat Exchanger .	15
Appendix D - Monitoring Data	18
Appendix E - Payback Estimate.	19
Appendix F - Work Plan.	20

INTRODUCTION

Increased concern for conservation of energy and natural resources led to the initial consideration by the Vermont Agency of Transportation to try a solar project. The added enhancement of Federal money to construct such a project resulted in the installation of a solar hot water system for the newly constructed Welcome Center on Interstate 93, in Waterford, Vermont. This report describes the construction, type, operation, and performance of the system used.

LOCATION AND BUILDING DESCRIPTION

The solar system was installed on a newly constructed Welcome Center on Interstate 93 in the town of Waterford, Vermont. See Location Map, Appendix A. The location is at latitude 44° -22' north and 71° -52' west longitude. The building is approximately 930 feet above sea level.

The building has a floor area of $2200 \pm$ square feet of which 1670 square feet are devoted to public use. The longitudinal axis of the building is 10° east of due south. The southern roof exposures are on a 39.8° incline and free of shading. See site plan, Appendix B.



Welcome Center - Southern Exposure

CLIMATOLOGICAL INFORMATION

Climatological data obtained from the U.S. Department of Commerce Environmental Data Service for the site of the Welcome Center is as follows:

Mean annual number of days maximum temperature 90°F and above ...	2
Mean annual number of days minimum temperature 32°F and below ...	180
Mean annual total heating degree days (base 65°F)	8500
Mean length of freeze-free period (days)	120
Normal monthly total precipitation (inches)	3.3
Mean annual number of days with 0.01 inch or more precipitation .	175
Mean annual total snowfall (inches)	100
Mean monthly percentage of possible sunshine for: January	40
July	40
Mean annual percentage of possible sunshine	40
Mean annual total hours of sunshine	1800
Mean daily solar radiation (Langleys) for: January	117
July	500

SOLAR SYSTEM DESCRIPTION

Construction on the building by Hare Construction Co., began in November, 1983. The solar portion of the project was constructed between March 23, 1983 and April 15, 1983. Normally, construction of the system would take two or three days, but in this case construction was not conducted in one continuous operation. The contractor obtained parts as construction progressed and performed many other operations at the same time.

Basically, the closed-loop system consists of four Grumman model #332A solar collectors, Grumman Sunstream CF-100A heat exchanger, X-trol #3 auxiliary pressure tank and Solarstream hot water heater tank. The closed-loop system used antifreeze to transfer heat from exterior mounted solar panels to the interior mounted heat exchanger where energy is transferred to the hot water system. This allows for year round operation. The collectors are 4' x 8', weighing 120 pounds per panel, insulated with 7.7 R value foam type insulation and single glazed with low iron tempered glass. Resulting transmissivity of the panel is 89%. Mounting brackets were manufactured to obtain ideal collection angles on the southern exposure roofs.



ROOF MOUNTED SOLAR PANELS

Panels were mounted in two separate banks of two panels each because of building design. The two banks were connected in series with the panels in each bank connected in parallel/reverse return.

The Sunstream heat exchanger module consists of a double-wall, center flow heat exchanger which provides insurance against potable water contamination; two sealed, no-maintenance circulator pumps, one for collector fluid and one for water; an expansion tank; check valve; relief valve; C-30 differential temperature controller with high-temp cut off; two manual hose bibs for easy filling; solar loop pressure temperature gauge, three position operating mode switch and molded cover. Manufacturer's detailed description and schematic of the heat exchanger can be found in Appendix C.



SUNSTREAM HEAT EXCHANGER

The hot water tank is a 120 gallon tank insulated to R-20. The top third can be heated with a backup 4500 watt electric element. The tank is tapped on top with four internal pipe legs of varied length extended into the tank to prescribed depths to gain maximum efficiency from the solar system. The system requires no other back-up. The Vermont Agency of Transportation plans of the hot water solar collector system are shown in Figure 1, page 7.



MONITORING EQUIPMENT AND PROCEDURES

Various monitoring equipment was used to keep records on solar fluid temperature, water temperature, ambient temperature and quantity of water used.

A C-100 differential temperature control/performance monitoring unit was installed to monitor the following items:

- Solar collector temperature
- Glycol temperature as it enters heat exchanger
- Glycol temperature as it exits heat exchanger
- Hot water temperature from heater tank as it enters heat exchanger
- Hot water temperature to heater tank as it exits heat exchanger
- Mechanical room temperature

- EXISTING AND PROPOSED FOR INTERFERENCE**
1. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 2. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 3. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 4. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 5. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 6. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 7. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 8. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 9. EXISTING COLLECTOR LINE REMAINS UNCHANGED
 10. EXISTING COLLECTOR LINE REMAINS UNCHANGED

- NOTES**
1. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 2. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 3. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 4. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 5. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 6. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 7. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 8. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 9. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 10. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL


- ASSUMPTIONS**
1. ABOVE GRADE FLOOR
 2. ABOVE GRADE FLOOR
 3. ABOVE GRADE FLOOR
 4. ABOVE GRADE FLOOR
 5. ABOVE GRADE FLOOR
 6. ABOVE GRADE FLOOR
 7. ABOVE GRADE FLOOR
 8. ABOVE GRADE FLOOR
 9. ABOVE GRADE FLOOR
 10. ABOVE GRADE FLOOR

STATE OF VERMONT	
AGENCY OF TRANSPORTATION	
PROJECT NO.	WATERFORD, VERMONT
PROJECT NAME	HOT WATER SOLAR COLLECTOR SYSTEM
DESIGNED BY	APRIL 18, 1982
CHECKED BY	APRIL 18, 1982
DATE	APRIL 18, 1982
PROJECT NO.	WATERFORD, VERMONT
PROJECT NAME	HOT WATER SOLAR COLLECTOR SYSTEM
DESIGNED BY	APRIL 18, 1982
CHECKED BY	APRIL 18, 1982
DATE	APRIL 18, 1982

- GENERAL NOTES**
1. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 2. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 3. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 4. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 5. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 6. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 7. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 8. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 9. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 10. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL

- TEMPERATURE SENSORS AT GRID SMALL VOLTAGE**
1. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 2. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 3. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 4. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 5. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 6. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 7. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 8. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 9. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL
 10. PROVIDE INSULATION TO ALL EXPOSED COLLECTOR TO EMBL

- GENERAL NOTES**
1. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 2. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 3. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 4. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 5. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 6. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 7. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 8. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 9. CONTRACT DRAWINGS ARE IN THIS DIAGRAM
 10. CONTRACT DRAWINGS ARE IN THIS DIAGRAM



SEE DIAGRAM 21 - PLUMBING - FOR INTERFERENCE WITH BUILDING PLUMBING SYSTEMS

SCHEMATIC DIAGRAM 17

In line thermometers were installed on water lines entering and exiting the hot water tanks.

Water meters were provided on the water supply to the building and on the inlet line to the hot tank.

Electrical supply lines to the solar equipment and the hot water heater were equipped with kilowatt-hours meters.

Readings were taken from the monitoring equipment at various time periods, ranging from two weeks to a month. The monitoring period was from June of 1983 to December of 1984, approximately 518 days. Due to a delay in the installation of the kilowatt meters, readings of the electrical usage were only taken from November, 1983 to November, 1984. Visits to the facility were all midday and under varied weather conditions. Periodically, temperature readings were taken by fulltime Welcome Center personnel.

Data was used to determine temperature exchanges between glycol and domestic water, heat exchange between glycol and solar collector, electrical energy used for heating hot water and operating solar equipment and quantities of water used.

RESULTS OF DATA OBTAINED

Traffic flow, accessible to the Welcome Center, averaged 1,050 vehicles per day and approximately 5,600 people used the facility during the monitoring period. Water meter readings showed that approximately 9% of the total water usage was hot water. Throughout the monitoring period, 122,718 gallons of water were used, of which 10,997 gallons were hot water. Daily usage of hot water fluctuated from 13 to 49 gallons and the temperature of non-tempered

hot water ranged from 120° to 185°F. On no occasion was there any report of shortage of hot water. Incoming water temperatures from the drilled water well ranged from a low 56°F during the coldest months to a high of 64°F during the summer months. On the average, water to the hot water tank was raised 90°F.

Electricity demands to operate the solar system equipment and maintain hot water on occasion when the solar system could not were minimal. Daily electrical usage of the solar equipment averaged 0.5 kilowatt hour, and ranged from a low of 0.2 to 0.8 kilowatt hour. During the summer and fall months, power to the electric heating element of the hot water tank was turned off because the solar system could more than adequately supply hot water. Average daily electrical usage when the electrical back-up was needed averaged 0.9 kilowatt hour and ranged from 0.3 to 2.5 hours, indicating that the solar system was supplying the majority of hot water.

Temperature readings of fluids passing through the heat exchanger revealed that at peak operating times the temperature of domestic hot water was raised an average of $10\pm^{\circ}\text{F}$, while glycol temperatures were lowered by $14\pm^{\circ}\text{F}$. The temperature of glycol from the collector during periods the system was collecting solar energy ranged from 130° to 212°F. After reviewing all the data, it is estimated that during the evaluation period, 97% to 99% of all hot water was supplied and maintained by the solar system. Detailed results of readings taken can be seen in Appendix D, page 18.

COST AND PAYBACK OF SOLAR SYSTEM

The contract cost of the completed solar system with back-up system was \$5,755.00. For the purpose of computing payback, \$355.00 for a conventional electric hot water heater was deducted from the total cost.

Yearly cost was based on the present rate of 8¢ per kilowatt hour, increasing 4% yearly, and increased water demands of 3% per year. Initial yearly cost figure was obtained from documented consumer data for an 80 gallon hot water tank with R-11 insulation jacket. Cost of operating the solar system was increased with considerations that the back-up electrical needs would increase with the increase in hot water demands. Maintenance fees for minor service and glycol changes were incorporated at 5 year intervals.

Another type of payback is the savings of an estimated 58,000 kilowatt-hours of electricity over a 10 year period.

Projections indicate that the cost of the solar system would be recovered by the 10th year of service. Payback Estimate Table may be seen in Appendix E, page 19.

PUBLIC INFORMATION DISPLAY

Signs were placed at the entrance to the building and within the building informing the public that the solar panels were assisting in supplying hot water for the Welcome Center.



On numerous occasions, the public questioned attendants on how well the system worked, or asked to see the system. The attendants themselves seemed impressed with how well the solar hot water system worked, becoming well informed and promoters of the system.


SUMMARY

A closed-loop domestic hot water solar system was installed in the newly constructed Waterford Welcome Center. Basic solar components were four Grumman model #332A solar panels, a Grumman Sunstream CF-100A heat exchanger and a Solarstream solar hot water heater tank. The solar hot water system was monitored for hot water demands and electricity usage over an 18 month period.

Daily usage of hot water for the entire evaluation averaged 21 gallons per day, or a total of 10,997 gallons. Temperatures of the water out of the solar system ranged from 120°F to 185°F. On no occasion was there a hot water shortage, even during the 8 months the power to the back-up system was turned off. Average daily electrical usage of the solar equipment was 0.4 kilowatt-hour per day. The back-up electric heat system required only an average of 0.9 kilowatt-hour per day.

The solar system provided 97% to 99% of all required hot water. At the present operating performance, it is expected that the solar system will provide virtually all the hot water need of the facility.

The added \$5,400.00 cost of the solar system will be fully recovered within ten years of service and will have saved approximately 58,000 kilowatt-hours of electrical power. The success of this solar project should be the stimulus for development of other solar energy projects for other rest areas and maintenance facilities.



[illegible][illegible]


DESCRIPTION OF SOLAR HEAT EXCHANGER

Control System

Circulators for the water and collector loops are activated whenever enough solar energy is available to increase the temperature of the water in the solar tank. Circulators are activated by a *differential controller* within the module, which is connected to one temperature sensor located at the collector and one temperature sensor located at the storage tank.

The differential controller is activated by the module *front panel selector switch*. Its functions are:

- ☐ ON. Circulators are manually activated regardless of whether solar energy is available.
- ☐ OFF. Circulators are inoperative.
- ☐ AUTO. The controller automatically activates the circulators when preset conditions are met. When the collector sensor is 20°F above the temperature of the tank sensor, the system is activated. When collector and tank sensors are within 3°F of one another, the system is turned off.



System Monitoring

An *indicator light* on the module front panel is operative when the selector switch is on AUTO. The light, when lit, indicates that necessary levels of solar energy are available, and that electrical current is being supplied to both circulators.

A *pressure/temperature gauge* located on the front panel monitors fluid pressure and temperature in the collector loop. Any leakage in the collector loop will be indicated by a substantial pressure drop. During normal system operation, the gauge will indicate gradual temperature increases. Collector loop fluid temperature is governed both by the intensity of the sun and by the temperature of water held in the storage tank.

Systems Precautions

Collector Loop Fluid

- ☐ Collector loop fluid is a solution of 50% ethylene glycol and 50% distilled water. System performance may be adversely affected unless proper proportions are maintained. An average installation will require four to six gallons of collector loop fluid. The recommended ethylene glycol solutions are listed on the following page. If these solutions are used, they need only be changed every FIVE YEARS.

section one System Operation

The CF-100A Module is designed to preheat water entering a conventional domestic water heater, thus reducing energy requirements.

The counterflow heat exchange module contains:

- ☐ A highly efficient double-wall exchanger
- ☐ Two low-power circulators
- ☐ A differential controller
- ☐ An expansion tank
- ☐ A pressure/temperature gauge
- ☐ Necessary switches and valves

Liquid Loops

This Grumman Sunstream system uses two separate liquid loops. The first is the *collector loop*, which connects solar collectors to the module and contains an anti-freeze solution.

A separate *water loop* connects the module to the storage tank, and contains potable water.

Antifreeze is pumped through solar collectors, where it is heated and returned to the module heat exchanger by the *glycol circulator*. Heat from the antifreeze is transferred to water circulated through the module heat exchanger.

As indicated, the counterflow heat exchanger is constructed of three copper tubes fitted inside each other. Water flows in one direction through the center tube, which is rifled to increase heat transfer surface. An antifreeze solution moves in the opposite direction through parallel passages in the outer tube. Between the two are passages which provide leak detection and prevent any contamination of the potable water supply.

The module *expansion tank* keeps collector loop pressure at acceptable levels. A *pressure relief valve* backs up the expansion tank, and will operate only in the event of multiple system failures.

Water heated by the module system replenishes energy removed by domestic hot water demands. Since most existing systems are thermostatically controlled, conventional energy sources will be drawn upon when solar-heated water does not meet domestic use/temperature requirements.




Figure 1. Model CF-100A Components

—Dow SR-1
—Dowgard

—Texaco P.T.
—Peak

—Shellzone
—Atlas Permaguard

DO NOT use any brand of antifreeze which contains leak inhibitors.

Circulator Pumps

Circulators are fluid lubricated. Failure to charge the collector and water loops prior to operation may result in permanent circulator damage.

The entire system must be leak-tight and free of air to operate efficiently.

Relief Valves

DO NOT isolate the water side of the module from the pressure relief valve located on the solar storage tank by valving without providing additional relief capability.

DO NOT isolate collectors by valving from the module expansion tank or collector loop pressure relief valve.

System Safety Features

High Limit Temperature Protection—Thermal overload switches within the module provide high limit temperature protection. The thermal overload component is attached to the module water inlet pipe and breaks supply voltage to both circulators whenever storage tank water temperature reaches 170°F. Impedance protection devices within the motor windings of both circulators will protect these units from going above 275°F.

Pressure within the collector loop is limited to about 50 psi by the module expansion tank, which accepts increased fluid volume under increased temperature conditions. Collector loop pressure is further controlled by a pressure relief valve which will not permit system pressure to exceed 75 psi. The relief valve will be activated only in the event of multiple component failures.

When the water main pressure is in excess of 80 psi, a pressure regulating valve should be installed to make sure that the solar system does not receive more than 80 psi of pressure. To make sure that the pressure regulating valve operates properly, it is recommended that a strainer be installed in front of the valve.

WATERFORD - WELCOME CENTER
SOLAR HOT WATER MONITORING

STATE OF VERMONT A.O.T.
MATERIALS & RESEARCH DIVISION

DATE OF READING	DAYS SINCE LAST READING	DAYS SINCE START OF STUDY	MECHANICAL RM. TEMP.	AMBIENT TEMP. OUTSIDE	COLLECTOR TEMP.	TO COLLECTOR	FROM COLLECTOR	DEGREES DIFFERENCE GYCOL TO & FROM COLLECTOR	HEAT EXCHANGER WATER IN	HEAT EXCHANGER WATER OUT	DEG. DIFF. WATER TO. & FROM HEAT EXCH.	GAL. HOT WATER USED SINCE LAST READING	GAL. HOT WATER USED PER DAY SINCE LAST READING	GAL. HOT WATER USED PER DAY SINCE BEGIN STUDY	GAL. WATER USED SINCE LAST READING	GAL. WATER USED PER DAY SINCE LAST READING	GAL. WATER USED PER DAY SINCE STUDY BEGAN	KILOWATT HR. USED FOR HOT WATER SINCE LAST READING/Daily	KILOWATT HR. USED FOR HOT WATER SINCE STUDY BEGAN	KILOWATT HR. USED FOR SOLAR SYSTEM SINCE LAST READING/Daily	KILOWATT HR. USED FOR SOLAR SYSTEM SINCE STUDY BEGAN
6-17-83	-	-	78	74	-	155	169	14	147	155	8	-	-	-	-	-	-	*	*	*	*
6-30-83	13	13	75	60	-	136	140	4	139	142	3	230.8	18	13	3377	260	260	*	*	*	*
7-08-83	8	21	78	76	-	152	170	18	136	147	11	296.0	37	25	3041	380	306	*	*	*	*
7-15-83	7	28	84	82	-	159	170	11	148	160	12	222.0	32	27	3132	447	341	*	*	*	*
7-26-83	11	39	88	80	212	175	182	7	169	174	5	284.6	26	27	4915	447	371	*	*	*	*
8-10-83	15	54	85	67	189	175	188	13	162	171	9	465.8	31	28	6630	442	391	*	*	*	*
8-30-83	20	74	76	68					124	131	7	543.8	27	28	7725	386	389	*	*	*	*
10-05-83	36	110	73	63	131	110	132	22	93	131	38	979.4	27	27	11149	310	363	*	*	*	*
10-14-83	9	119	75	63	158	128	146	18	115	125	10	442.7	49	29	3989	443	369	*	*	*	*
11-01-83	18	137	79	58	168	154	149	5	156	156	-	272.7	15	27	2811	156	341	*	*	*	*
11-15-83	14	151	74	40	147	132	147	15	117	127	10	229.0	16	26	1435	103	319	*	*	6 0.43	0.43
1-04-84	50	201	71	28	System was not operating at time of insp.							667.0	13	23	4344	87	261	*	*	11 0.22	0.27
1-18-84	14	215	69	12								222.5	16	23	1011	72	249	*	*	3 0.21	0.26
2-03-84	16	231	68	40								243.8	15	22	1231	77	237	*	*	8 0.50	0.30
2-27-84	24	255	79	30	167	153	169	16	138	148	10	413.3	17	22	2968	124	227	61 2.54	2.54	9 0.33	0.31
3-22-84	24	279	73	45	148	133	118	15		140		312.9	13	21	2084	87	214	37 1.54	2.04	10 0.42	0.32
5-02-84	41	320	69	41	System was not operating at time of insp.							544.3	13	20	6259	153	207	13 0.32	1.25	20 0.49	0.36
5-23-84	21	341	81	84	184	169	183	14	156	165	9	309.9	15	20	3094	147	203	10 0.48	1.10	11 0.52	0.38
6-20-84	28	369	76	71	182	167	181	14	154	164	10	445.6	16	19	5594	200	203	9 0.32	0.94	18 0.64	0.41
7-10-84	20	389	76	76	151	131	150	19	136	141	5	537.7	27	20	7615	381	212		0.82	12.5 0.63	0.43
8-03-84	24	413	80	78	172	157	171	14	144	153	9	693.5	29	20	9198	383	222		0.71	18.5 0.77	0.46
8-31-84	28	441	76	70	123	109	124	15	101	107	6	906.0	32	21	11136	398	233		0.62	20 0.71	0.48
9-18-84	18	459	79	76	212+	158	152	6	146	153	7	453.6	25	21	5706	317	236		0.57	11 0.61	0.49
11-16-84	59	518	70	42								1280.4	22	21	14274	242	237	27 0.46	0.55	33 0.56	0.50

*Metering equipment not yet installed.

PAYBACK ESTIMATE

Years of Service	Yearly Cost to Operate an Electric Hot Water Heater*	Total Cost of Electricity	Cost of Electricity for Solar System ** and Back-Up System	Total Cost of Solar System \$5,400.00 Initial Cost
1	\$485.00	\$ 485.00	\$32.00	\$5432.00
2	\$509.00	\$ 994.00	\$35.00	\$5467.00
3	\$535.00	\$1529.00	\$39.00	\$5506.00
4	\$561.00	\$2090.00	\$43.00	\$5549.00
5	\$590.00	\$2680.00	\$47.00 plus maintenance cost of \$150	\$5746.00
6	\$619.00	\$3299.00	\$52.00	\$5798.00
7	\$650.00	\$3949.00	\$57.00	\$5855.00
8	\$682.00	\$4631.00	\$63.00	\$5918.00
9	\$717.00	\$5348.00	\$69.00	\$5987.00
10	\$752.00	\$6100.00	\$76.00	\$6063.00
11	\$790.00	\$6890.00	\$83.00 plus maintenance cost of \$200	\$6346.00

Payback in Ten Years

*Calculation based on initial rate of 8¢/kWh; 5% increase in hot water usage and 4% increase in electric rates.

**Calculation based on same rates as used for conventional heater but increased for solar not being able to supply total increased demand.

STATE OF VERMONT
AGENCY OF TRANSPORTATION
MATERIALS & RESEARCH DIVISION

WORK PLAN FOR
CATEGORY III EXPERIMENTAL PROJECT

SOLAR ENERGY FOR HIGHWAY USES
(REGION 15 DEMONSTRATION PROJECT NO. 52)
Work Plan 82-R-5

OBJECT OF EXPERIMENT

To design, construct, and monitor the performance of a solar assisted hot water heating system.

PROJECT AND LOCATION

Interstate 93 Welcome Center at Waterford, Vermont. Project Waterford - St. Johnsbury IR 93-1(5) (Number tentative as of 2/24/82)

SOLAR APPLICATION

Solar assisted domestic hot water heating.

TYPE OF SYSTEM

Active solar thermal energy system.

CONVENTIONAL ENERGY SYSTEM BEING ASSISTED

Electric hot water.

SYSTEM DESCRIPTION

Type of collector - Solar panels, closed fluid system
Type of storage - Heat exchanger and 120 gallon storage tank.
Backup system - Conventional electric hot water system.

DEMAND POTENTIAL

The solar system is designed to meet 60% of the annual demand load.

ADDITIONAL CONSERVATION MEASURES

Other conservation measures specified in the facility include triple glazed windows, entrance vestibules, 12 inch insulation in ceilings and 5½ inches in walls, wood stove, and peak power controller for off peak power.

PRELIMINARY COST ESTIMATE

Engineering and Design Costs	\$ 500.00
Total Installed Cost of Solar Energy System with Backup	\$8000.00
Cost of Monitoring Equipment, Evaluation and Reports	\$4650.00
Cost of Public Information Display	\$ 75.00
Total Installed Cost of a Conventional Energy System	<u>\$ 750.00</u>
Total Amount of FHWA Demonstration Projects Funds Requested	\$12475.00

CONTRACT TASKS

- A. Prepare preliminary design and life cycle cost analysis.
- B. Prepare monitoring plan and finalize design. Prepare public information display.
- C. Procure and install solar energy system with monitoring equipment.
- D. Operate, maintain, and monitor system.
- E. Periodic data reporting and evaluation report.

DURATION OF STUDY

The experimental feature will be evaluated for a minimum of two years following completion of the installation.

Reviewed by:



R. F. Nicholson, P.E.
Materials & Research Engineer

Date: 3/3/82

Vermont Agency of Transportation
Materials & Research Division
March 3, 1982